

TYPICAL CONTROL PANEL WITH ELECTRICAL METER ON EQUIPMENT RACK


TYPICAL CONTROL PANEL WITH ELECTRICAL METER ON UTILITY POLE

- NOTES:
- ELECTRIC METER AND PRIMARY DISCONNECT MOUNTED TO STAINLESS STEEL UNISTRUT ON BACK SIDE OF EQUIPMENT RACK.
 - EMERGENCY GENERATOR RECEPTACLES: RUSSELL & STOLL, JRSB 1044FR (100 amp), 2504FR (200 amp).
 - ALL POWER AND CONTROL WIRING SHALL BE CONTINUOUS (NO SPLICES).
 - PANEL MOUNTED TO STAINLESS STEEL UNISTRUT BY WELDED TABS ON PANEL.
 - SERVICE DISCONNECT SWITCH, NEMA 3R STAINLESS STEEL OR NON-METALLIC ENCLOSURE, ROUSSEL, SERVICE ENTRANCE RATED WITH NEUTRAL BAR, GROUND AND SERVICE TERMINALS PER N.E.C. 250-26. ALL SWITCH HARDWARE SHALL BE STAINLESS STEEL.
 - THE CONTRACTOR SHALL VERIFY THE POWER SERVICE AVAILABLE FROM THE POWER COMPANY AND COORDINATE THE LIFT STATION CONTROL PANEL AND ALL OTHER EQUIPMENT WITH THE AVAILABLE SERVICE PRIOR TO THE INSTALLATION. THE CONTRACTOR SHALL INSURE THAT THE SERVICE IS A 120V/120V HIGH-LEG SERVICE. THE CONTRACTOR SHALL INSURE THAT THE 120V LOADS IN THE LIFT STATION CONTROL PANEL ARE NOT CONNECTED TO THE HIGH-LEG.

- NOTES:
- THE LIGHT POLE MUST BE PLACED TO WHERE THE LIGHT FIXTURES AND THE FRONT OF CONTROL PANEL AND ILLUMINATES THE ENTIRE STATION AREA. THE LIGHT POLE SHALL BE 20' HIGH AND THE LIGHT POLE SERVICE UTILITY POLE WHERE THE FLOOD LIGHT CAN BE MOUNTED AND THE POLE IS LOCATED WHERE THE STATION WILL BE ILLUMINATED AS DESCRIBED ABOVE.
- WEATHERPROOF SWITCH FOR FLOODLIGHTS TO BE MOUNTED TO OVERHANG OF LIGHT POLE TO PREVENT THE USE OF A TRIP.
- FLOODLIGHT, 400 WATT HIGH PRESSURE SODIUM, 120VAC SINGLE POLE, NEMA WESTLOCK 2 FOOT, 12/3 COND PREMOUNTED WITH WALL MOUNT BRACKET CAT NO. TP005-8B-120-SF-1P-C2-PR-FMB-TTRV (4) 3/8" x 3" LONG ANCHORS LITHONIA TYPE FPMB WALL BRACKET WEATHERPROOF BOX WITH TWO HUBS IN THE BOTTOM 2 FOOT, 12/3 COND CONDUIT LITHONIA TYPE TTRV FULL VISOR (3) 1/2" x 1/2" x 1/2" CONDUIT

REQUIRED LIFT STATION ELECTRICAL DATA

SERVICE SIZE _____	AMPS _____	VOLTS _____	PHASE _____	WIRE _____
AVAILABLE SHORT CIRCUIT AMPS FROM UTILITY CO. _____ SCA _____				
OVER CURRENT PROTECTION EQUIPMENT INTERRUPTING CAPACITY _____ AIC _____				




LIGHT POLE



GROUNDING NOTES:

- GROUNDING INSTALLATION SHALL BE IN ACCORDANCE WITH REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE AND SUCH LOCAL CODES WHICH HAVE PRECEDENCE.
- LOCATION OF GROUNDING LOOP IS SHOWN DISAGREEMENTALLY. EXACT LOCATION TO MAINTAIN CLEARANCE FROM FOOTERS SHALL BE DETERMINED IN THE FIELD.
- PROVIDE 3/4" DIA. x 10' LONG COPPERPLATED SECTIONAL GROUND RODS COUPLED TOGETHER AS REQUIRED TO GIVE A MAXIMUM SYSTEM RESISTANCE OF 5 OHMS TO GROUND.
- TOP OF GROUNDING RODS SHALL BE 30" BELOW GRADE.
- NO.2/0 AWG BARE STRANDED COPPER GROUND WIRE IS TO BE USED FOR THE MAIN SERVICE GROUNDING CONDUCTOR AND ALL OTHER GROUNDING WIRING. NO.2/0 AWG BARE STRANDED COPPER GROUND WIRE IS TO BE USED FOR THE TAPS AT A MINIMUM. THE FOLLOWING ITEMS SHALL BE BONDED TO THE MAIN GROUND LOOP:
 - A. MAIN SERVICE GROUNDING ELECTRODE CONDUCTOR
 - B. CONTROL PANEL PERMITS DISCONNECT
 - C. UTILITY METER PER UTILITY COMPANY REQUIREMENTS
 - D. CORNER AND GATE FENCE POSTS
 - E. LIGHT POLE AND/OR UTILITY POLE
 - F. GENERATOR
 - G. TELEMETRY ANTENNA GROUND ROD
 - H. TELEMETRY ANTENNA GROUND ROD
- GROUND WIRE RUNS, BETWEEN POINT OF CONNECTIONS, SHALL BE AS SHORT AND STRAIGHT AS POSSIBLE.
- ALL SURFACES TO BE GROUNDING SHALL BE THOROUGHLY CLEANED TO BARE METAL BEFORE ATTACHING GROUND CONNECTION.
- GROUND RESISTANCE SHALL NOT EXCEED 5 OHMS. THE RESISTANCE TO GROUND SHALL BE MEASURED BY A LOW RESISTANCE TYPE OF MEGGER, AS DESCRIBED IN N.E.C. ARTICLE 250-6. THE TEST SHALL BE PERFORMED BY THE METHOD AS DESCRIBED IN JAMES G. BIDOLE PUBLICATION NO. 25-1-3. THE RESISTANCE SHALL BE MEASURED WITH THE GROUND POINT ISOLATED AND THE CONTACT POINTS SHALL BE CLEANED TO REMOVAL OF THE SOIL. GROUND TESTS SHALL BE NO TREATMENT OF THE SOIL AROUND THE GROUND RODS TO IMPROVE THE RESISTANCE.
- IF THE MEASURED RESISTANCE TO GROUND DOES NOT MEET THE REQUIRED VALUE, EXTENSIONS SHALL BE COUPLED TO THE ROD OR ADDITIONAL RODS SPACED 10' APART SHALL BE DRIVEN AND CONNECTED BY NO.2/0 AWG BARE STRANDED COPPER CABLE.
- WHERE GROUNDING WIRE RISES TO ELECTRICAL EQUIPMENT, COLUMNS, POSTS, VESSELS, ETC. THROUGH EARTH OR CONCRETE SLABS, THE WIRE SHALL BE PROTECTED BY SCHEDULE 80 PVC CONDUIT.
- ALL BELOW GRADE OR CONCRETE SLAB GROUNDING CONNECTIONS SHALL BE MADE USING THE EXOTHERMIC WELDING PROCESS, CAPPED OR APPROVED EQUAL.

TYPICAL GATE GROUNDING DETAIL



AERIAL FEED POWER POLE




TYPICAL CONTROL PANEL WITH ELECTRICAL METER ON UTILITY POLE


- NOTES:
- ELECTRIC METER AND PRIMARY DISCONNECT MOUNTED TO STAINLESS STEEL UNISTRUT ON BACK SIDE OF EQUIPMENT RACK.
 - EMERGENCY GENERATOR RECEPTACLES: RUSSELL & STOLL, JRSB 1044FR (100 amp), 2504FR (200 amp).
 - ALL POWER AND CONTROL WIRING SHALL BE CONTINUOUS (NO SPLICES).
 - PANEL MOUNTED TO STAINLESS STEEL UNISTRUT BY WELDED TABS ON PANEL.
 - SERVICE DISCONNECT SWITCH, NEMA 3R STAINLESS STEEL OR NON-METALLIC ENCLOSURE, ROUSSEL, SERVICE ENTRANCE RATED WITH NEUTRAL BAR, GROUND AND SERVICE TERMINALS PER N.E.C. 250-26. ALL SWITCH HARDWARE SHALL BE STAINLESS STEEL.
 - THE CONTRACTOR SHALL VERIFY THE POWER SERVICE AVAILABLE FROM THE POWER COMPANY AND COORDINATE THE LIFT STATION CONTROL PANEL AND ALL OTHER EQUIPMENT WITH THE AVAILABLE SERVICE PRIOR TO THE INSTALLATION. THE CONTRACTOR SHALL INSURE THAT THE SERVICE IS A 120V/120V HIGH-LEG SERVICE. THE CONTRACTOR SHALL INSURE THAT THE 120V LOADS IN THE LIFT STATION CONTROL PANEL ARE NOT CONNECTED TO THE HIGH-LEG.

- NOTES:
- WEATHERHEAD AS REQUIRED BY THE POWER COMPANY
- CONDUCTOR TERMINATION HEIGHT AS REQUIRED BY THE POWER COMPANY
- CONCRETE POLE PRESTRESSED TYPE II, SERVICE CABLE TERMINATION HEIGHT REQUIRED BY THE POWER COMPANY
- METER AS REQUIRED BY POWER COMPANY
- LIGHTNING ARRESTOR
- SERVICE DISCONNECT SWITCH, NEMA 3R, STAINLESS STEEL, OR NON-METALLIC ENCLOSURE, SERVICE ENTRANCE RATED WITH NEUTRAL BAR AND BONDING PER N.E.C. 250-28.
- 3/4" AIC GALVANIZED STEEL CONDUIT WITH ELECTRODE TO COPPERPLATED GROUND RODS MINIMUM (2) LONG.
- CONTINUE GROUNDING CONDUCTOR TO SERVICE UTILITY POLES AND GROUND ROD
- 2" MINIMUM CONDUIT TO WET WELL (TWP)
- POLE MOUNTED SERVICE DISCONNECT AT METER
- 3/4" CONDUIT W/GROUNDING ELECTRODE TO COPPERPLATED GROUND RODS MINIMUM (2) LONG.
- CONDUIT SEALS TYPE EDS SEE DETAIL NO.1
- 30"W x 36"H SERVICE PANEL NEMA 3R, 304 S.S.
- GENERATOR RECEPTACLE
- ALARM HORN
- SECONDARY CONTROL PANEL MCB
- SWITCH
- GENERATOR RECEPTACLE
- FLASHER RED WARNING LIGHT
- MODE 4


CORNER POST GROUNDING DETAIL



CHAIN LINK FENCE



TYPICAL LIFT STATION GROUNDING PLAN



ISSUE CODE	A PRELIMINARY	B DESIGN
C ISSUES	D CONSTRUCTION	E APPROVAL
DESIGN	CHK'D BY:	SCALE: NONE
DRAWN BY: JHH-34243	DATE: 9/1/07	ENR.

DRAWING TITLE	LIFT STATION ELECTRICAL DETAILS
AREA	WASTEWATER ELECTRICAL DETAILS
JOB NO.	
REV.	

CITY OF LAKE WALES	ISSUE CODE
AREA	CITY-OF-LAKE-WALES